

BOQ -Furniture work (Solicitation # 191N6520Q0081)

(ISC office - East Building Basement: Room # B-08A,B-08B,B-09A,B-09B, B-09C & B-10A6)

US Embassy(New Delhi),Chanakyapuri.

Date:-September 3rd, 2020 (Revised) --R2**Name of work:ISC remodeling--Basement East building**

SI No	Description	Quantity	Unit	Rate (Rs)	Amount (Rs)	GST (Rs)	Total Cost (Rs)
	SCOPE OF WORK:- Dismantling & Disposal of Existing unwanted Furniture; and supply & installation of new furniture as per listed size and quantity in accordance with attached layout/drawing; Scope of Work. Fabric, shade, paint, laminate color selection will be upon receipt of availability of options and vendor will provide final drawing with dimensions after receipt of the order and taking actual site measurements.						
A	<u>Removal and Disposal Of Existing Fixed Furniture from Embassy Premises.</u>						
1	Removal of Existing Cubicles nos. # 01 - 19 -complete with overhead units, under counter storage units and partition panels etc.(please refer existing furniture layout drawing)	19.00	nos.				
2	Removal of Existing continious wooded over head storage unit from Room #B-08B (please refer existing furniture layout drawing)	1.00	nos.				
3	Shifting of Existing Conference table along with chairs from Room # B-08B to Room # B-08A (please refer proposed furniture layout drawing)	1.00	nos.				
B	<u>Fabricate, Supply and Installation on site CUBICLES</u>						
1	Room B-08A (Cubicle nos. #17+#18):- Modular Tile Based "L-SHAPED" work station cubicles,with one each 1'-6"(D) X1'-6"(W)X 2'-4"(H) PEDESTAL UNIT (3 DRAWERS) (MOVABLE) under the desk , and one each 2'-0"(L)X1'-6"(H)X1'-3"(D) MODULAR TOP HUNG OVER HEAD STORAGE UNIT hung on 2'-0" wide partition panel. SIZE:- 6'-6"(L) X 5'-0"(W) X 2'-0"(D) and 5'-6"(H). Each Cubicle to have 3 nos. of partition panels 5'-6"(H)(3'-4" solid+2'-2" glass) } + 1no. of partition panel 5'-6"(H) (total solid) } only. Lengths of the partition panel to be in accordance to attached layout.Panel thickness not to exceed 3". Each cubicle to have 2 raceways--1no. @ skirting level +1 no. @ table top level.The table top shall be at 2'-5" height from the floor.Each workstation to have one pin up board and one white board each.	2.00	nos.				

2	<p>Room B-08B (Cubicle nos. #1 to #4 + # to #7 to #10):- Modular Tile Based "L-SHAPED" work station cubicles,with one each 1'-6"(D) X1'-6"(W)X 2'-4"(H) PEDESTAL UNIT (3 DRAWERS) (MOVABLE) under the desk , and one each 2'-0"(L)X 1'-6"(H)X1'-3"(D) MODULAR TOP HUNG OVER HEAD STORAGE UNIT hung on 2'-0" wide partition panel.</p> <p>SIZE:- 6'-6"(L) X 5'-3"(W) X 2'-0"(D) and 5'-6"(H).</p> <p>Each Cubicle to have 3 nos. of partition panels 5'-6"(H)(3'-4" solid+2'-2" glass) } + 1no. of partition panel 5'-6"(H) (total solid) } only.Lengths of the partition panel to be in accordance to attached layout.Panel thickness not to exceed 3". Each cubicle to have 2 raceways--1no. @ skirting level +1 no. @ table top level.The table top shall be at 2'-5" height from the floor.Each workstation to have one pin up board and one white board each.</p>	8.00	nos.				
2	<p>Room B-08B (Cubicle nos. #5 & #6):-Modular Tile Based "L-SHAPED" work station cubicles,with one each 1'-6"(D) X1'-6"(W)X 2'-4"(H) PEDESTAL UNIT (3 DRAWERS) (MOVABLE) under the desk , and one each 2'-0"(L)X 1'-6"(H)X1'-3"(D) MODULAR TOP HUNG OVER HEAD STORAGE UNIT hung on 2'-0" wide partition panel.</p> <p>SIZE:- 6'-6"(L) X 5'-9"(W) X 2'-0"(D) and 5'-6"(H).</p> <p>Each Cubicle to have 3 nos. of partition panels 5'-6"(H)(3'-4" solid+2'-2" glass) } + 1no. of partition panel 5'-6"(H) (total solid) } only.Lengths of the partition panel to be in accordance to attached layout.Panel thickness not to exceed 3". Each cubicle to have 2 raceways--1no. @ skirting level +1 no. @ table top level.The table top shall be at 2'-5" height from the floor.Each workstation to have one pin up board and one white board each.</p>	2.00	nos.				
3	<p>Room B-08B (Cubicle no. #11):-Modular Tile Based "L-SHAPED" work station cubicles,with one each 1'-6"(D) X1'-6"(W)X 2'-4"(H) PEDESTAL UNIT (3 DRAWERS) (MOVABLE) under the desk , and one each 3'-0"(L)X 1'-6"(H)X1'-3"(D) MODULAR TOP HUNG OVER HEAD STORAGE UNIT hung on 2'-0" wide partition panel.</p> <p>SIZE:- 5'-6"(L) X 6'-6"(W) X 2'-0"(D) and 5'-6"(H).</p> <p>Each Cubicle to have 3 nos. of partition panels 5'-6"(H)(3'-4" solid+2'-2" glass) } + 1no. of partition panel 5'-6"(H) (total solid) } only.Lengths of the partition panel to be in accordance to attached layout.Panel thickness not to exceed 3". Each cubicle to have 2 raceways--1no. @ skirting level +1 no. @ table top level.The table top shall be at 2'-5" height from the floor.Each workstation to have one pin up board and one white board each.</p>	1.00	nos.				
4	<p>Room B-09A (Cubicle no. #12):-Modular Tile Based "U-SHAPED" work station cubicles,with one each 1'-6"(D) X1'-6"(W)X 2'-4"(H) PEDESTAL UNIT (3 DRAWERS) (MOVABLE) + 1'-8"(D) X2'-6"(W)X 2'-4"(H) LATERAL UNIT (2 DRAWERS)(MOVABLE) under the desk , and three equal MODULAR TOP HUNG OVER HEAD STORAGE UNIT hung on entire length of 8'-0" wide partition panel.</p> <p>SIZE:- 8'-0"(L) X 8'-0"(W) X 2'-0"(D) and 3'-4"(H).</p> <p>Each Cubicle to have 3 sides of partition panels 3'-4"(H)(total solid) + 1no. of partition panel 5'-6"(H) (total solid) } only.Lengths of the partition panel to be in accordance to attached layout.Panel thickness not to exceed 3". Each cubicle to have 2 raceways--1no. @ skirting level +1 no. @ table top level.The table top shall be at 2'-5" height from the floor.Each workstation to have one pin up board and one white board each.</p>	1.00	nos.				

5	Room B-09B (Cubicle no. #13+#14):- Modular Tile Based "L-SHAPED" work station cubicles,with one each 1'-6"(D) X1'-6"(W)X 2'-4"(H) PEDESTAL UNIT (3 DRAWERS) (MOVABLE) under the desk , and two equal MODULAR TOP HUNG OVER HEAD STORAGE UNIT hung on entire length of 6'-3" wide partition panel. SIZE:- 6'-3"(L) X 5'-6"(W) X 2'-0"(D) and 5'- 6"(H). Each Cubicle to have 2 nos. of partition panels 5'-6"(H)(3'-4" solid+2'-2" glass)} + 2 nos. of partition panel 5'-6"(H) (total solid) } only.Lengths of the partition panel to be in accordance to attached layout.Panel thickness not to exceed 3". Each cubicle to have 2 raceways--1no. @ skirting level +1 no. @ table top level.The table top shall be at 2'-5" height from the floor.Each workstation to have one pin up board and one white board each.	2.00	nos.				
6	Room B-09C (Cubicle no. #15):- Modular Tile Based "L-SHAPED" work station cubicles,with one each 1'-6"(D) X1'-6"(W)X 2'-4"(H) PEDESTAL UNIT (3 DRAWERS) (MOVABLE) under the desk , and three equal MODULAR TOP HUNG OVER HEAD STORAGE UNIT hung on entire length of 7'-0" wide partition panel. SIZE:- 7'-0"(L) X 6'-0"(W) X 2'-0"(D) and 5'- 6"(H). Each Cubicle to have 2 sides. of partition panels 5'-6"(H)total solid)} only.Lengths of the partition panel to be in accordance to attached layout.Panel thickness not to exceed 3". Each cubicle to have 2 raceways--1no. @ skirting level +1 no. @ table top level.The table top shall be at 2'-5" height from the floor.Each workstation to have one pin up board and one white board each.	1.00	nos.				
7	Room B-09C (Cubicle no. #16):- Modular Tile Based "L-SHAPED" work station cubicles,with one each 1'-6"(D) X1'-6"(W)X 2'-4"(H) PEDESTAL UNIT (3 DRAWERS) (MOVABLE) under the desk , and three equal MODULAR TOP HUNG OVER HEAD STORAGE UNIT hung on entire length of 7'-0" wide partition panel. SIZE:- 7'-0"(L) X 4'-9"(W) X 2'-0"(D) and 5'- 6"(H). Each Cubicle to have 2 sides. of partition panels 5'-6"(H)total solid)} only.Lengths of the partition panel to be in accordance to attached layout.Panel thickness not to exceed 3". Each cubicle to have 2 raceways--1no. @ skirting level +1 no. @ table top level.The table top shall be at 2'-5" height from the floor.Each workstation to have one pin up board and one white board each.	1.00	nos.				
8	Room B-010A6 (Cubicle no. #19+#20):- Modular Tile Based "L-SHAPED" work station cubicles,with one each 1'-6"(D) X1'-6"(W)X 2'-4"(H) PEDESTAL UNIT (3 DRAWERS) (MOVABLE) under the desk only. SIZE:- 7'-0"(L) X 4'-9"(W) X 2'-0"(D) and 3'- 4"(H). Each Cubicle to have 2 sides. of partition panels 3'-4"(H)total solid)} only.Lengths of the partition panel to be in accordance to attached layout.Panel thickness not to exceed 3". Each cubicle to have 2 raceways--1no. @ skirting level +1 no. @ table top level.The table top shall be at 2'-5" height from the floor.Each workstation to have one pin up board and one white board each.	2.00	nos.				
c	Supply and Installation on site STORAGE CABINET						
9	Room B-08A+B-08B:- Size--3'-0"(W)x1'-6"(D)x5'-5"(H) -- Stand alone Storage cabinet as per attached picture .Top half to be -2 door cabinet;lower half to have 3 equal file drawers.Cabinet to match with the Cubicles finalised. Subject to Customer Approval.	7.00	nos.				
	GST (Goods & Services Tax)						
	Freight Charges (If applicable)						

	TOTAL COSTS						
	GRAND TOTAL						

SPECIAL COMMENTS:-

1. Workstation to be in 25mm thk Pre laminated MDF.
2. All storage units to be in CRCA MS sheets.
3. Overhead units to have top hung shutter with slide in mechanism. Lockable shutter with no handle. Will be mounted on Partition panel. 1 Task light to be provided under each Overhead unit. Task light to be recessed and built in the O/H unit. Or permanently fixed. Light to be CE/UL listed.
4. Under counter units to have castor wheels-4 nos. each—2 lockable ones. Lockable drawers with recessed in handles.
5. Each cubicle will have 1 White board + 1 Pin up board. Approval on finish of Pin up board to be taken from customer before production.
6. Entire workstation will be tile based knock down type. Hight of Partition panel to be etermined from drawing. All other partition panels (except for #1 pin up and #1white board) will be CRCA MS Sheets.
9. In House Embassy staff will pull the electrical, data and telephone lines in accordance with workstation installation.
10. Furniture to provide 5 years warranty.
11. Existing cubicles only will be disposed by finalized vendor out from Embassy premises. No temporary storage space will be given to store the furniture.
12. Furniture to be fire retardant and sustainable; Provision of relevant certificates is mandatory.
13. Color, fabric, type, finish of all furniture to be approved by customer before actual production. In soft copy.
14. Swatch samples of finished to be provided to customer for future verification.
15. Vendor will have to visit site twice. Once for removal of existing furniture and second for installation on new furniture. Interval period between the two shall be shared with the awarded vendor at the commencement of work.
16. **Contractor shall provide by- back cost for all old furniture.**
17. All under listed documents pertaining to the new workstation provided to site must be given along with the material to the customer:-
 - I. Test reports (as per specifications.)
 - II. Technical Specifications
 - III. Installation manual.
 - IV. Warranty Documents.
 - V. User Guidelines.
 - VI. Any other product related information.